Questions & Answers

Title:	Wheels or Feet and Transfer Station Height				ID:
				0295	
Date in:		Response:	Model:	Author:	
2007-09-15		2007-09-15	STX500	СМа	

Wheels: The STX500 have no wheels as standard. If someone asks us to install wheels, we would take the wheels we install on the STX1000. The wheels we are using cause the transfer station height to be increased by ~1 inch (when feet at min. height).

